

2023 Project list district 1

West shore dr detour rd for culvert replacement

Finish west shore drive for paving

Finish ditching from willow st to end of the road clean up first part of road fix areas of concern

Shoulder west shore drive an willow st

Once paving of the road in done there will be new gravel shoulders added

Ditching on h road

Ditching to be done from lakeside drive to the apple orchard

Culvert replacement on mann rd

Replace Two 12 inch culverts on Mann rd that are rotten and one is collapsed and Brushing cutting as well

shoulder work on goose pond

Use grader and fix shoulders on goose pond rd and rehab ditch's add gravel were needed

Tree work and road side mowing

Hawk Rd Repave

Replace 15 inch culvert with Maine dot at the start of the road

Rip out old hot top build road up a few inches to improve drainage all other culverts have been replaced shoulder road once paving is done

H-Road pond by Pine Ridge CampGround

Joint project with York County soil and water

Remove beaver damn rip rap around inlet of culvert and stabilize the banking and railroad ties

Rehab the ditches that are both sides of the road and put in rock check damns

All projects could be subject change

Will Langley

District 1 Road commissioner